

PANEL SCHEDULE LP-1

Panel: LP-1, new	Voltage: 120/208 V, 3 phase, 4 wire	Bus: 225 A	Main: 200 A main breaker
Type: 42-circuit panelboard	Mounting: surface	Location: electrical room	Fed from: transformer T1, sheet E-001
Interrupting rating: 10 kA	Breakers: bolt-on	Circuits in use: 11	Spare breakers: 4, not wired

Ckt	Description	VA	Breaker
1	Lighting, reading room (16 troffers)	640	20A/1P
3	Lighting, children's area (12 troffers)	480	20A/1P
5	Lighting, lobby (4) and program room (6) (10 troffers)	400	20A/1P
7	Lighting, staff workroom (4), electrical room (1), washrooms (2) (7 troffers)	280	20A/1P
9	Exit signs (4) and emergency battery units (3)	50	20A/1P
11	Spare		20A/1P
13	Spare		20A/1P
15	Space		
17	Space		
19	Space		
21	Space		
23	Space		
25	Space		
27	Space		
29	Space		
31	Space		
33	Space		
35	Space		
37	Space		
39	Space		
41	Space		

Load summary	VA
Lighting, 45 troffers at 40 W	1800
Exit signs and emergency battery units	50
Receptacles, 30 at 180 VA	5400
Total connected load	7250

Ckt	Description	VA	Breaker
2	Receptacles, reading room west and north walls (5)	900	20A/1P
4	Receptacles, reading room south and east walls (5)	900	20A/1P
6	Receptacles, children's area (6)	1080	20A/1P
8	Receptacles, lobby (2) and program room (4)	1080	20A/1P
10	Receptacles, staff workroom (6)	1080	20A/1P
12	Receptacles, electrical room (1) and washrooms (1)	360	20A/1P
14	Spare		20A/1P
16	Spare		20A/1P
18	Space		
20	Space		
22	Space		
24	Space		
26	Space		
28	Space		
30	Space		
32	Space		
34	Space		
36	Space		
38	Space		
40	Space		
42	Space		

SCHEDULE NOTES

- 1. Provide a 20A/1P bolt-on breaker for every circuit in use and for every spare listed. Spaces have no breaker.
- 2. Device and fixture counts in the circuit descriptions match sheets E-101 and E-102.

Brightline Consulting Engineers Ltd.

Electrical engineering. Project BCE-26-114

PROJECT

Quillbrook Public Library, Main Floor
Electrical Fit-out

2150 Heron Crescent, Quillbrook, Alberta

OWNER

Quillbrook Public Library Board

REVISIONS

Rev	Description	Date
0	Issued for tender	2026-09-08

SCALE

Not to scale

SHEET TITLE

Panel Schedule LP-1

SHEET

E-002